

Schedule of Rate

Name of work:- Construction of connecting road from ECE building to New Academic building, NIT Silchar.
Completion Period:- 30 Days

OR:
CR:
OM:

Sl no	Item Description	Unit	Quantity	Rate in fig	Rate in word	Amount
1	Surface Dressing of the ground including vegetation and inequalities not exceeding 15 Cm deep and disposal of rubbish , leads upto 1.5 m. All kind of soil	sqm	210.00			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	cum	20.00			
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :Cement mortar 1:3 (1 cement : 3 coarse sand)	sqm	54.00			
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	3.00			
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (a) 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size) (b) 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	cum	2.10			
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights. Foundations, footings, bases of columns, etc. for mass concrete	sqm	13.20			

21/20/21
Lidya

OR:
CR:
OM:

Sl no	Item Description	Unit	Quantity	Rate in fig	Rate in word	Amount
7	15 mm cement plaster on rough side of single of half brick wall of mix : 1:4(1 cement : 4 coarse sand)	sqm	77.00			
8	Dismantling of existing chainlink fencing with brick wall (approx 6.00 sqm)	job	1.00			
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	1155.00			
10	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	75.00			
	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete.					

[Signature]

[Signature]

OR:
CR:
OM:

Sl no	Iteam Description	Unit	Quantity	Rate in fig	Rate in word	Amount
11	(A) Ridges plain (500 - 600mm)	Rm	25.00			
	(B) Crimp curve	sqm	50.00			

Total =

Rupees

Signature of the Agency

8/12/21